NEW WORK PLAN

BASE BID

- AREAS INDICATED IN YELLOW - PAINT ONLY:

WALLS TO BE PREPPED & PAINTED.

DOOR FRAMES TO BE PREPPED & PAINTED

- AREAS INDICATED IN GREEN - PAINT & CARPET

WALLS TO BE PREPPED & PAINTED

DOOR FRAMES TO BE PREPPED & PAINTED.

EXISTING CARPET & VINYL BASE TO BE REMOVED & PROPERLY DISPOSED OFFSITE.

CARRY OUT ANY NECESSARY FLOOR PREP & INSTALL NEW CARPET TILE & VINYL BASE.

- AREAS INDICATED IN PURPLE - CARPET ONLY:

EXISTING CARPET & VINYL BASE TO BE REMOVED & PROPERLY DISPOSED OFFSITE. CARRY OUT ANY NECESSARY FLOOR PREP & INSTALL NEW CARPET TILE & VINYL BASE.

- ACT CEILING TILE REPLACEMENT

REPLACE (500) 2'X4' ACT CEILING TILES THROUGHOUT THE BUILDING

COORDINATE WITH CITY OF CHARLOTTESVILLE PM TO COORDINATE EXACT TILES TO BE REPLACED.

ADD/ALT#001 - ADDITIONAL PAINTING SCOPE

- AREAS INDICATED IN PURPLE:

WALLS & DOOR FRAMES TO BE PREPPED & PAINTED AS WELL AS CARPET REPLACEMENT

ADD/ALT#002 - ADDITIONAL ROOMS

- AREAS INDICATED IN RED:

WALLS TO BE PREPPED & PAINTED.

DOOR FRAMES TO BE PREPPED & PAINTED.

EXISTING CARPET & VINYL BASE TO BE REMOVED & PROPERLY DISPOSED OFFSITE.

CARRY OUT ANY NECESSARY FLOOR PREP & INSTALL NEW CARPET TILE & VINYL BASE.

EXISTING FURNITURE


- ROOMS MARKED AS 'FC' WILL BE EMPTY & CLEARED OF FURNITURE.
- ROOMS MARKED AS 'CO' HAVE OFFICE PARTITION WALLS WHICH WILL NEED TO BE DISASSEMBLED, MOVED OUT OF THE WAY FOR THE WORK TO TAKE PLACE AND THEN REASSEMBLED IN THE SAME LOCATION AND CONDITION AS BEFORE.
- OTHER ROOMS MAY HAVE SOME MISCELLANEOUS FURNITURE WHICH NEEDS TO BE MOVED OUT OF THE WAY FOR THE WORK TO PROCEED AND THEN PUT BACK IN THE SAME LOCATION AND CONDITION AS BEFORE.
- CORRIDORS WILL BE EMPTY & CLEARED OF FURNITURE.

PHASING PLAN

SEE SHEET A02 FOR DETAILS REGARDING PROPOSED PHASING & SCHEDULE PLAN

PRODUCT SPECIFICATIONS

- CARPET IN CORRIDOR
- INTERFACE CT102 COMMON THEME 103985 STEEL, OR APPROVED EQUAL
- CARPET IN OFFICES
 - INTERFACE CT101 COMMON THEME 103973 SLATE, OR APPROVED EQUAL
- PAINT
 - SHERWIN WILLIAMS EMERALD. OR APPROVED EQUAL
- ACT CEILING TILE
 - ARMSTRONG CORTEGA 769 24"x48". OR APPROVED EQUAL
- VINYL BASE
 - JOHNSONITE TRADITIONAL WALL BASE, OR APPROVED EQUAL



Page:

AVENUE

ROSE HILL

1138

Public Works

Department Facilities [

Development street, N.W. Ile, VA 22903

Develor Street,

acilities 305 4th

X

귑

NEW WORK

PHASING PLAN

PHASING/SCHEDULE PLAN

- THE PROJECT WILL BE TAKING PLACE IN AN OCCUPIED FACILITY.
- THE WORK IS TO BE BROKEN OUT INTO SEPARATE PHASES.
- EACH PHASE IS TO BE INDEPENDENT OF EACH OTHER. THE CONTRACTOR IS NOT TO START WORK ON THE NEXT PHASE UNTIL THE CURRENT PHASE IS 100% COMPLETE & READY FOR THE CLIENT TO MOVE BACK IN TO.
- THE DURATIONS GIVEN OPPOSITE ARE THE STATED TARGET DURATIONS FOR THE PROJECT. THE CONTRACTOR IS TO PLAN TO ACHIEVE THESE DURATIONS. IF THE CONTRACTOR DEEMS THAT THESE ARE NOT ACHIEVABLE OR THEY WANT TO PROPOSE A DIFFERENT PHASING PLAN THEN THEY ARE TO PROPOSE AN ALTERNATE TO THE CITY OF CHARLOTTESVILLE PM TO REVIEW & APPROVE.
- THE PAINTING WORK IN THE UPPER FLOOR PUBLIC WAITING ROOMS THAT IS SHOWN AS 'NON-CLINIC-DAYS'. THIS PHASE SHOULD BE BROKEN OUT OVER MULTIPLE WEEKS AND BE CARRIED OUT WHEN THE CLINIC IS CLOSED TO THE PUBLIC (FRIDAYS).
- THE PAINTING WORK IN THE LOWER FLOOR PUBLIC WAITING ROOMS THAT IS SHOWN AS 'NON-CLINIC-DAYS'. THIS PHASE SHOULD BE BROKEN OUT OVER MULTIPLE WEEKS AND BE CARRIED OUT WHEN THE CLINIC IS CLOSED TO THE PUBLIC (THURSDAYS).
- PHASES SHOWN AS 'WEEKEND' CAN BE BROKEN OUT OVER MULTIPLE WEEKS. WORK CAN TAKE PLACE ON SATURDAYS OR SUNDAYS. COORDINATE WITH CITY OF CHARLOTTESVILLE PM.

COMMUNAL OFFICES (230, 232, 238 & 246)

- THESE COMMUNAL OFFICES ARE FULL OF OFFICE CUBICLE PARTITION SYSTEMS.
- IT IS THE CONTRACTORS RESPONSIBILITY TO CAREFULLY DISASSEMBLE THE PARTITIONS AND STORE WITHIN THE WORK AREA IN SUCH A WAY THAT THE CARPET CAN THEN BE PARTIALLY INSTALLED. THEN THE CONTRACTOR IS TO MOVE THE PARTITIONS ONTO THE NEWLY INSTALLED CARPET AND THEN COMPLETE THE CARPET INSTALLATION.
- THE CONTRACTOR IS TO PROTECT THE NEWLY INSTALLED CARPET WHILE THE PARTITIONS ARE BEING MOVED AROUND.
- ONCE THE CARPET INSTALLATION IS COMPLETE THE CONTRACTOR IS THEN TO REASSEMBLE THE PARTITIONS IN THE SAME LOCATION AND CONDITION AS BEFORE.

FREE CLINIC ROOMS

- THE ROOMS AND OFFICES MARKED AS 'FC' WILL BE EMPTY & CLEARED OF FURNITURE.

OFFICES (290,291,292,293 & 123)

- THERE WILL BE MISCELLANEOUS DESKS & FURNITURE IN THESE ROOMS.
- IT IS THE CONTRACTORS RESPONSIBILITY TO CAREFULLY MOVE THIS FURNITURE OUT OF THE WAY TO ALLOW THE WORK TO TAKE PLACE. THEN ONCE THE WORK IS COMPLETE MOVE THE FURNITURE BACK TO THE SAME LOCATION (& IN THE SAME CONDITION) AS BEFORE.

ADDITIONAL TIME ALLOCATION FOR ADD/ALT #001

- IF ADD/ALT #001 IS SELECTED THE CONTRACTOR WILL BE GIVEN THE FOLLOWING ADDITIONAL TIME FOR EACH PHASE:
- ROOM # 290, 291, 292, 293 5 ADDITIONAL DAYS
- ROOM # 230 3 ADDITIONAL DAYS
- ROOM #232 3 ADDITIONAL DAYS
- ROOM #238 4 ADDITIONAL DAYS
- ROOM #246 4 ADDITIONAL DAYS
- ROOM # 123 3 ADDITIONAL DAYS
- 3 FC OFFICES 3 ADDITIONAL DAYS
- IF ADD/ALT #001 IS SELECTED THE CONTRACTOR THE SUBSTANTIAL/FINAL COMPLETION DATE WILL BE EXTENDED BY 25 WORK DAYS (5 WEEKS).

ADDITIONAL TIME ALLOCATION FOR ADD/ALT #002

- IF ADD/ALT #001 IS SELECTED THE CONTRACTOR WILL BE GIVEN THE FOLLOWING ADDITIONAL TIME FOR EACH PHASE:
- PHASE 1 5 ADDITIONAL DAYS
- PHASE 2 5 ADDITIONAL DAYS
- IF ADD/ALT #002 IS SELECTED THE CONTRACTOR THE SUBSTANTIAL/FINAL COMPLETION DATE WILL BE EXTENDED BY 10
 WORK DAYS (2 WEEKS).

